



# JORDAN K. VENTURES

Borehole Drilling, Geophysics, Plumbing, Water Treatment, Pump Installation, Mechanization, Building & Electricals

Tel: 0249-643118/0274-585127/0203620786

E-mail: jordankpeh@yahoo.com

<b>BILL OF QUANTITIES FOR BOREHOLE DRILLING, MECHACHANIZATION &amp; INSTALLATION OF CONCRETE OVERHAED STORAGE</b>					
No	Description	Unit	Qty	Unit Price GH¢	Total GH¢
A1	Mobilization	Lump	1	500	500
A2	Demobilization	Lump	1	500	500
A3	Geophysical Investigation	Lump	1	2000	2000
<b>B</b>	<b>Drilling</b>				
B1	Drilling through Overburden and highly weather rock	Meters	15	200	3000
B2	Drilling through fresh rock	Meters	85	150	12,750
<b>C</b>	<b>Construction</b>				
C1	supply and install PVC Plain	Meters	6	350	2100
C2	supply and install PVC Screen	Meters	15	400	6000
C3	Supply and place gravel packing	Meters	20	50	100
C4	Supply cement, mix and place grout above gravel pack	Meters	1	100	100
C5	Back fill annulus above grout seal	Meters	1	100	100
C6	supply cement, mix and place above backfill	Meters	1	100	100
<b>D</b>	<b>Borehole development</b>				
D1	Borehole development	Hours	1		5000
D2	Pump Test	Lump	1		4000
<b>Sub Total</b>					<b>36,250</b>
<b>NOTE;EXTRA ROD DRILLING PER 5METERS 1200 COST</b>					
<b>E</b>	<b>Installation of submersible pump and accessories</b>				
E1	Supply and installation of submersible pump, cables, pe pipe and accessories (1.5HP Pump)	lump	1		9000
E2	Chemical and Bacteriological water Analysis		1	1500	1500
<b>Sub total</b>					<b>10,500</b>



# JORDAN K. VENTURES

*Borehole Drilling, Geophysics, Plumbing, Water Treatment, Pump Installation, Mechanization, Building & Electricals*

Tel: 0249-643118/0274-585127/0203620786

E-mail: jordankpeh@yahoo.com

<b>F</b>	<b>construction of concrete Overhead platform for Rambo 1000 polytanks (1)</b>				
F1	Supply Cutting and binding of iron rods for re-enforcement				8000
F2	Setting out and excavation for pillars				500
F3	Cement		35	100	3500
F4	Sand	trip	1	2500	2500
F5	Stone	tip	1	3000	3000
F6	Feeling Sand	tip	1	1000	1000
F7	Casting of foundation concrete, Pilers lying, feeling and top concrete				3000
F8	Casting of concrete for fetching point, lying of 6" bock, lying of tiles and fixing of 3 fetching stand taps				7000
F9	Feeling of the construction part of the house	trip	1	2000	2000
<b>Sub Total</b>					<b>30,500</b>
<b>G</b>	<b>Supply and installation of water storage tanks and pipe lines</b>				
G1	Supply and installation of 1no- Rambo 1000 liters poly tanks	Item	1	12,400	12,400
G2	Supply and installation of pipes and accessories	Item	1	2,500	2,500
G3	Excavation of trenches, laying of pipe lines and covering of trench.	Item	1	500	500
G4	3 Stand pipe and 3 fetching point		6	200	1200
G5	painting			2000	2000
<b>Sub Total</b>					<b>18,600</b>
<b>GRAND TOTAL</b>					<b>90,850</b>



# JORDAN K. VENTURES

*Borehole Drilling, Geophysics, Plumbing, Water Treatment, Pump  
Installation, Mechanization, Building & Electricals*

Tel: 0249-643118/0274-585127/0203620786

E-mail: jordankpeh@yahoo.com

---

## Summary

Geophysics, drilling, construction and development (A1 to D2)	36,250
Installation of submersible pump and accessories (E1 to E2)	10,500
construction of concrete Overhead platform for Rambo 1000 polytanks (1) (F1 to F9)	30,500
Supply and installation of water storage tanks and pipe lines (G1 to G5)	18,600
<b>GRAND TOTAL</b>	<b>95,850</b>

**NOTE: EXTRA ROD DRILLING PER 5METERS 1200 COST.  
: HYDRO FRACTURE.**